Items of work	Approximate quantity	Unit	Tender rate at which each work will be worked out
9. Teakwood windows with panelled and glazed half shutters complete.	100	S.ft.	
10. Ventilators of teakwood with glazed shutters rectangular.	8¾	,,	
11. Ventilators of teak wood with glazed shutters circular.	62/7	,,	
12. Burnt stone slabs dressed by one line ...	523	,,	
13. Do roughly dressed ..	209	,,	
14. Stone wall plates	176	R.ft.	
15. Roofing with first class Bassel Mission tiles on teak wood reepers, etc., complete.	12·84	Sqr.	
16. Teak wood work wrought and put up with tarring.	43·62	C.ft.	
17. Ridge tiles set in mortar	68½	R.ft.	
18. Chunam border	112	,,	
19. Dormon long rolled steel Beams and Joists with lead lift and paint.	47·92	C.W.T.	
20. Jack arched terraced roof 9″ thick ..	11·83	Sqr.	
21. Burnt brick in mortar. Cornice work with plaster	210	R.ft.	
22. Plain parapet with burnt brick in mortar and chunam plaster.	208	,,	
23. Flooring with first class Bassel Mission tiles 9″ square on 3″ concrete bed with cement pointing.	3·36	Sqr.	
24. Kadapah slab flooring on 3″ concrete bed and cement pointing.	5·32	,,	
25. Concrete flooring with plaster	4·56	,,	
26. Sinks with spouts, etc.	Lump	sum	
27. Chunam plaster	76·18	Sqr.	
28. White Washing	55·27	,,	
29. Colour Washing	20·22	,,	
30. Galvanized iron sheet water spouts ..	16	Each	
31. Cement pointing	4·42	Sqr.	
32. Ventilating tiles (Bassel Mission)	6	Each	
33. Sirks and wovens, for kitchens and back rooms	Lump	sum	
34. Grinding stones	2	Each	
35. Gravel flooring	3 1/3	C.yd.	
36. Coping with burnt brick in mortar (including chunam plastering).	14½	R.ft.	
37. Tarring to walls of latrine	Lump	sum	
38. Boring hole in slab (9″ diameter)	1	Each	
39. Levelling ground, etc.	Lump	sum	
40. Stone year-board	1	Each	
41. Aligarh locks with duplicate keys 3″ ..	8	,,	
42. Teak wood windows with battened shutters complete.	50¾	Sq.ft.	

B. ABDUR RAHMON,
President, District Board.

TUMKUR DISTRICT.

Notification dated 30th October 1929.

It is hereby notified for the information of the general public that under section 17 of the Village Panchayet Regulation, Mr. Veerappa, is appointed as a member of Mallasandra Village Panchayet, Tumkur Taluk, in place of Mr. Surappa, who left the place for Madhugiri.

G. B. HEBLIKAR,
Deputy Commissioner.